

119 Coolidge Avenue - Contributing

This is a two-story side-gabled Colonial Revival style dwelling built ca. 1920. The house has an exterior of weatherboard siding, a roof of asphalt shingles with gable returns, an exterior brick chimney and a continuous brick foundation. On the main (N) façade is a centrally sited entrance beneath a gable roof entry porch supported by Tuscan columns with an arched ceiling. The main entrance retains its original, four-light and four-wood panel door with original four-light glass and wood sidelights above which is an original wood sunburst panel. Windows are original, six-over-one double hung wood sash. Centrally located on the upper façade is a square, multi-light Craftsman-style leaded glass window.



Located to the rear of the dwelling is a ca. 1930, one-bay, frame garage with a gable roof of asphalt shingles with gable returns, an exterior of weatherboard siding and a ca. 1950, thirty-two wood panel overhead track door.

- Contributing